REVISIONS:
Rev A: SS 06.11.09
Double toddler swing retained.
Bin relocated.
2 x benches added.
Spinner moved.
Rev B: TS 13.01.10
Construction Issue
Jumping Discs omitted.
1 Timber deck omitted
Safety matt area reduced.
Area of new planting reduced.

PLAY MOUND
formations made using excavated material from old play area

EARTHWORKS
ditch and bank in front of wall to form Ha Ha

EXISTING PLAY BOAT
retained and refurbished

Section A-A
Indicative 'Ha-Ha' design

'SUPERNOVA'
roundabout supplied by Kompan
safety zone shown
in dashed line

EXISTING CRADLE SWING
refurbished, repositioned and reduced from 4 bays to 2
safety zone shown
in dashed line

CLIMBING LOGS

EXISTING PLANTING

EXISTING PATH
widened to 1.5m

5 WAY SWING
supplied by Sik Holz
safety zone shown
in dashed line

HA-HA

MACADAM

NEW FENCELINE
existing fence refurbished and re-instated

SELF BINDING GREY GRAVEL

SELF BINDING GOLDEN GRAVEL

SANDPIT

PLAY BOULDERS

PLAY BARK

UNILOG WALL
300mm height

Zone of critical fall height
(for info only)

'SPRIE NET'
climbing net supplied
by Kompan
safety zone shown
in dashed line

CABLE SLIDE
existing equipment
re-installed

EXISTING BOUNDARY PLANTING

EXISTING CONCRETE
LOW WALL
retained & refurbished

TIMBER DECKS
at varying heights as indicated
To contractor design

MIXED NATIVE & ORNAMENTAL PLANTING

MINI-BEAST LOG STACK
logs of varying lengths set in ground packed together

PLAY HUT
supplied by Sik-Holz
safety zone shown
in dashed line

NEW FENCELINE
existing fence refurbished and re-instated

- EXISTING TREES
- PROPOSED TREES to be supplied by client and planted in this contract
- PROPOSED PLANTING refer to specification for mix
- LONG MEADOW GRASS (Mowing regime part of site management)
- NEW LAWN Turfing
- Open textured macadam over existing base course (see lable)
- SELF BINDING GRAVEL rolled 25mm to dust gravel in contrasting colours (Grey, Golden) As supplied by Imag laid over existing base (see lable)
- SAFETY RUBBER 'Tigermulch' recycled rubber crumb supplied by Star Rubber laid over existing sub-base
- PLAY BARK 300mm depth sterilised bark chipping (see lable)
- PLAY SAND 300mm depth play sand
- MATTA PLAY rubber safety matting laid over new turf
- TIMBER EDGING BOARDS to all edge restraints
- +0.3 PROPOSED TIMBER DECKING to contractors design
- HA-HA Gabion walls backfilled using concrete rubble facing and excavated fill from site demolition. 1:3 Grass bank to inside face. Gabion & foundations design by contractor
- BENCHES / PICNIC BENCHES
- GATE TO PLAY AREAS 1.5m self closing gate
- Boundary fence site boundary fences to be kept in place. Play area fence to be lifted, re-fettled and re-installed to new fence line
- +(13.25) Existing level
- +13.45 Proposed Level
- New fence line of re-installed fencing
- RB Litter bin

GROUNDWORK
CHANGING PLACES CHANGING LIVES
Groundwork London
East Office
6 Lower Clapton Road
London E5 0PD
tel: 020 8985 1755
fax: 020 8510 5400
www.groundwork4london.org.uk

Job Title: BLYTHE HILL SE6

Drawing Title: GENERAL ARRANGEMENT PLAN

Client: LB LEWISHAM

Date:	Scale:
23.10.09	1:200@A2
Drawn By: TS	Checked By: SS

Job Ref:	Drawing Ref:	Revision:
LE027	LE027__001	B